

6-23-21W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **BEACON RESOURCES & STERLING DRILLING**

SEC. 6 T. 23 R. 21W

FARM **Mooney "E"** NO. 1

LOC. C NW NW

TOTAL DEPTH **4572'**

COUNTY **Hodgeman**


COMM. **8-6-68**

COMP. **8-17-68**

SHOT OR TREATED

CONTRACTOR **Sterling Drilling**

ISSUED **11-16-68**



CASING

20	10	
15	8	5/8" 329' cem w/ 175 sx
12	6	
13	5	1/2" 4566' cem w/ 100 sx

ELEVATION **2307' KB**

PRODUCTION **PMP 17 BOPD Plus**
165 BWPD/ MISS 4566-72

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 179	Surface Shale
179 - 332	Shale Shells
332 - 405	Shale
405 - 1200	Shale and Shells
1200 - 2680	Lime and Shale
2680 - 2760	Lime
2760 - 3500	Lime and Shale
3500 - 3700	Lime
3700 - 3727	Lime and Shale
3727 - 3930	Lime
3930 - 3985	Lime and Shale
3985 - 4250	Lime
4250 - 4300	Lime and Shale
4300 - 4572	Lime

Ran 8 joints 8 5/8" OD Surface Casing
 322 - 58' Cemented @ 329 K.B. with 175
 sacks quick set cement. Plug down @
 1:20 PM, 8-6-68

Ran 11 1/2 joints 5 1/2" 11# J-55 8rd
 Casing 4566.17' threads off. Set @
 4566' with 100 cu. ft. salt saturated
 cement. Plug down at 5:00 PM, 8-17-68

TOPS: SMP	
Anhydrite	1441
Heebner	3894
Lansing	3962
Base KANSAS City	4326
Fort Scott	4485
Cheorkee	4510
Mississippi Chat	4563
TD	4572