

Wichita, Kansas

MAY 9 1969

ROTARY DRILLING LOG

31-235-21W
Curt

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 12-29-68

Rotary Drilling Completed 1-9-69

LOCATION: Hall "K" No. 1, App. C SE SW Sec. 31-235-21W
HODGEMAN County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Ran 13 jts used 28# 8 5/8" casing set @ 259'KB. Cemented with
160 sacks cement. Completed 6:15 P.M. Circulated December 29, 1968.

Ran 147 jts, 9.5# 4 1/2" casing set @ 4578' K.B. Cemented with 135
sacks common cement. Plug down 1:45 PM January 10, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

259	Shale & Shells	C. F. S.
750	Shale, Shells, & Red Bed	4346
785	Shale & Shells	4365
810	Blain	4380
885	Shale & Shells	4505
1000	Sand	4520
1440	Anhydrite	4536
1950	Shale & Shells	4583
2175	Shale & Lime	
2730	Lime	
2880	Lime & Shale	Slope Tests
3050	Shale & Lime	2000
3400	Lime & Shale	2500
3580	Shale & Lime	3000
3850	Lime & Shale	3500
4536	Lime	4000
4563	Lime Chert RTD	4500

S. L. M.
3990