

31-23-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HERMAN GEORGE KAISER, ETAL
Farm- Hall "F" No. 1

SEC. 31 T. 23 R. 21W
C SE SE

Total Depth. 4606'
Comm. 4-24-62 Comp. 5-10-62
Shot or Treated.
Contractor. H-30, Inc.
Issued. 1-12-63

County Hodgeman
KANSAS



Elevation. 2330' DF

Production. 30 BOPD

CASING:

8 5/8" 251' cem w/150 sx.
4 1/2" 4544' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale & shells	250
shale, shells & red bed	560
shale & shells	870
red bed, shells & sand	1355
red bed, shale & shells	1405
anhydrite	1419
shale & shells	1715
shale & lime	2435
lime & shale	2535
lime	2745
lime & shale	2800
shale & lime	3360
lime & shale	3460
shale & lime	3533
lime & shale	3600
shale & lime	3865
lime	3920
lime & shale	4040
lime	4425
lime & shale	4470
lime	4514
lime & shale	4530
lime	4576
Mississippi	4606 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite (Scout)	1405
Heebner	3875
Toronto	3896
Brown Lime	3960
Lansing	3972
Base Kansas City	4314
Cherokee	4472
Mississippi	4562