

508 East Murdock
Wichita, Kansas

ROTARY DRILLING LOG

32-23-21W

Distributed By

KANSAS GEOLOGICAL SOCIETY

JAN 25 1969

COMPANY: PICKRELL DRILLING COMPANY 508 East Murdock **Rotary Drilling Commenced** 11/26/68
705 4th National Bank Bldg. **WICHITA, KANSAS 67214**

LOCATION: Wichita, Kansas **Rotary Drilling Completed** 12/6/68
~~Greason "B" No. 1, C SW SW Sec. 32-23S-21W~~
Hodgeman County, Kansas

Prod - Oil

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Ran 17 jts used 28# 8 5/8" casing set at 261' KB. Cemented with 165 sacks cement. Circulated. Completed 6:45, 11/26/68.

Ran 139 jts of 14# 5 1/2" casing, set 13 feet of bottom at 4552' KB. Cemented with 125 sacks of 50-50 Pozmix followed by 60 sacks common cement. Circulated. Plugged down @ 5:15 A.M. 12/7/68.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

...105	Surface clay & Sand	<u>C. F. S.</u>
261	Shale	4343
605	Blue Shale	4365
790	Red Beds	4487
808	Blaine	4503
880	Red Beds, Shale & Shells	4528
1005	Sand	4559
1415	Shale, Shells & Red Bed	4565
1455	Anhydrite	
1870	Shale & Shells	<u>Slope Test</u>
2250	Shale w/Lime	2000
2760	Lime	2500
3515	Shale & Lime	3000
3685	Shale	3500
3965	Lime & Shale	4000
4420	Lime	4500
4487	Lime & Shale	
4528	Lime	
4565	Lime & Chert	<u>S. L. M.</u>
4565	RTD & LTD	