

Wichita, Kansas

AUG 23 1969

ROTARY DRILLING LOG

32-235-21W

COMPANY: Pickrell Drilling Company  
705 4th National Bank Bldg.  
WICHITA, Kansas

Rotary Drilling Commenced 6/4/69

Rotary Drilling Completed 6/15/69

LOCATION: Gleason "B" #2, SW NE SW Sec. 32-235-21W  
Hodgeman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD:

Ran 8 jts. 28# 8-5/8" surface casing set @ 293' KB. Cemented with 165 sacks. Completed 6:30 PM June 4, 1969. Circulated.

Ran 152 jts. 5-1/2" 15-1/2# casing @ 4623'. Cemented with 125 sacks 50-50 pozmix plus 16 sacks common. Plug down 7:30 AM June 16, 1969

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

*oil*

80	Top Soil Clay
175	Shale
293	Shale & Shells
660	Shale & Red Bed
715	Shale - Shells
730	Blain
1430	Shale - Shells
1470	Anhydrite
1800	Shale & Shells - Lime
2235	Shale
2485	Shale & Lime
3020	Lime & Shale
3946	Shale & Lime
3965	Lime - Shale
4555	Lime
4605	Lime & Shale
4626	Mississippian & RTD

C. F. S.

4393  
4420  
4540  
4555  
4626

S. L. M.

Strap 3946

Slope Tests

2000  
2500  
3000  
3500  
4000  
4500



The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling above well as reflected by the Daily Drilling Reports.