

3-23-68

**KANSAS GEOLOGICAL SOL.**  
**KANSAS WELL LOG BUREAU - KANSAS WELL BOARD**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**808 EAST MURDOCK - WICHITA, KANSAS**

COMPANY **BEARDMORE DRILLING**

REG. 3 T. 23 22W  
 COR. C SE SW

FARM **Baldrey** NO. 3

COUNTY **Hodgeman**

TOTAL DEPTH **4415'**

DATE 2-4-68

DATE 2-14-68

DRILLER

Walters Drilling

DATE 6-8-68

KANSAS


CASING

PP  
15  
15  
15

5/8" 317' cem w/ 225 BX

ELEVATION **2183' KB**

PRODUCTION P 52 BOPD PLUS 60Z

W/ Miss 4404-15

FIGURES INDICATE DEPTH BY FORMATION

0 - 85	Surface Clay and Sand		
85 - 317	Shale		
317 - 750	Clay	TOPS: LOG SMP	
750 - 910	Sand	Anhydrite	1296
910 - 1124	Red Bed	Heebner	3728
1124 - 1296	Red Bed and Shale	Lansing	3798
1296 - 1335	Anhydrite	Base Kansas City	4152
1335 - 1405	Shale and Shells	Marmaton	4169
1405 - 1810	Shale	Fort Scott	4322
1810 - 2229	Shale and Lime	Cherokee	4346
2229 - 2780	Lime	Mississippi	4398
2780 - 2915	Lime and Shale	Osage	4403
2915 - 3060	Lime	TD	4415
3060 - 3263	Lime and Shale		
3263 - 3305	Shale		
3305 - 3885	Shale and Lime		
3885 - 4415	Lime		
<u>4415</u>	<u>Rotary Total Depth</u>		

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY   
 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me  
 this 11th day of March, 1968.