

3-23-22W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Baldrey "A" No. 2

SEC. 3 T. 23 R. 22W
C NW SW

Total Depth. 4422'
Comm. 7-7-65 Comp. 7-18-65
Shot or Treated.
Contractor. Co. Tools.
Issued. 10-16-65

County Hodgeman
KANSAS



Elevation. 2181' K.B.

Production. Pmp. 124 BOPD

CASING:

8 5/8" 310' w/225 sx cem
5 1/2" 4413' w/125 sx cem.

Figures Indicate Bottom of Formations.

surface clay	40
sand	60
shale, shells	285
shale	311
shale, shells	410
red bed, shale	664
Blaine Anhydrite	702
shale	652
sand	95 5
shale	1272
S.C. Anhydrite	1308
Anhydrite	1328
shale, shells	2190
lime, shale	3820
lime	4343
shale, lime	4406
lime	4422
Rotary Total Depth	

TOPS:

B/Blaine (Sc)	664
Stone Corral	1292
Heebner	3732
Toronto	3747
Lansing	3797
B/Lansing	4155
Marmaton	4175
Cherokee lime	4331
Mississippi Warsaw	4405
Mississippi Osage	4412

DST #1 - 4412-22. Op. 1 hr. Rec.
1685' oil, BHP 1420#-1420# 30"
FP 108# - 636#.

No electric log run