

KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

3-23-22W

COMPANY PETROLEUM INC.

SEC. 3- T. 23 R. 22W

LOC. C NW SE

FARM Houseman

NO. 1

TOTAL DEPTH 4418'

COMM. 4-22-67

COMP. 5-3-67


SHOT OR TREATED

CONTRACTOR Garvey Drlg.

ISSUED 8-19-67

COUNTY Hodgeman

KANSAS



CASING

20

10

15

8 5/8" 248' cem w/ 175 sx

12

6

13

5 1/2" 4416' cem w/ 100 sx

ELEVATION 2182' KB

PRODUCTION 93 BOPD PLUS 30% W

Grav 31.2 Miss 4405-10

FIGURES INDICATE BOTTOM OF FORMATIONS

50' Sand with Shells
250' Shale and Red Bed
750' Red Bed
890' Sand
910' Red Bed
1285' Red Bed and Shale
1315' Anhydrite
2085' Shale and Shells
2640' Lime
2720' Lime with Shale
2895' Lime
3280' Lime and Shale
3445' Shale and Lime
3765' Lime and Shale
3850' Shale and Lime
3930' Lime with Shale
4216' Lime
4360' Lime and Shale
4400' Lime
4408' Mississippi Chert
4418' Chert
4418' RTD

TOPS: LOG

Heebner	3728
Lansing	3795
Marmaton	4165
Ft. Scott	4321
Mississippi	4396
Mississippi Osage	4400

State of Kansas

County of Barton

SS