


KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 9 T. 23 R. 22 E

NE
Loc. SE SE

County Hodgeman

640 Acres
N

Locate well correctly

Elev.: Gr. 2221'

DF 2223' KB 2226'

API No. 15 — 083 — 20,363
County Number

Operator

O. A. Sutton

Address 800 Sutton Place Wichita, Kansas 67202

Well No.

#1

Lease Name

Clifton

Footage Location

990

feet from (N) (S) line

330

feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Richard K. Grant

Spud Date

May 5, 1974

Total Depth

4515'

P.B.T.D.

Date Completed

May 15, 1974

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	24#	513'	common	300	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

rator

O. A. Sutton

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No.

1

Lease Name

Clifton

S 9 T 23 S R 22 ^{EX}
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM


NAME

DEPTH

DST #1, 4466-4515', open 90 min.,
strong blow weaking to dead; rec. 3140'
muddy salt water; ~~IB~~ slightly gas-cut;
IBHP 1440# 45 min., FBHP 1440#
45 min.; FP 449-1340#.

Log tops:
Anhydrite 1337 (plus 889
Heebner 3784 (-1558)
Lansing 3855 (-1629)
BKC 4206 (-1980)
Marmaton 4226 (-2000)
Pawnee 4316 (-2090)
Ft. Scott 4380 (-2154)
Cherokee 4406 (-2180)
Mississippian 4460 (-2234)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



A handwritten signature in cursive script, appearing to read 'E. G. McNeil'.

Signature

Exploration Manager

Title

October 17, 1974

Date