

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas

14-23-22W


Company - FLYNN OIL CO.  
Farm - Osborne

No. 1

SEC. 14 T. 23 R. 22W  
SE SE SW

Total Depth. 4560  
Comm. 5-30-51 Comp. 6-14-51  
Shot or Treated.  
Contractor.  
Issued. 7-21-51

County. Hodgeman  
KANSAS



2200 (m)

Elevation. 2203 R.B.

2202 AB (2nd)

Production. Dry

CASING:

8 5/8" 218' com. w/125 sx.

Figures Indicate Bottom of Formations.

collar	7
surface clay	40
sand & shale	105
shale & shells	1325
anhyd.	1358
red bed, shale & strks	
of salt	1750
salt & shale	1800
shale	2030
shale & shells	2185
lime, shells, shale &	
lime	2290
lime & shale	2560
lime	2695
lime & shale	3775
lime	4560
Total Depth	

Tops:	
Anhyd.	1325
Hoebner	3802
Kansas City	3879
Marmaton	4217
Chert Congl.	4458
Miss. dolo.	4486

4048-50 limestone cream, mod. xyln  
fossiliferous & oolitic, fair porosity  
No. sat. No. odor.  
4100-20 Limestone tan, fine to mod.  
xyln, soft, fair to good oolitic  
por. No sat. No odor.  
4511-18 Dolo. cream, fine xyln, poor  
to fair vuggy por. No sat. No odor.  
4525-30 Dolo. as above  
4537-60 Dolo. cream, fine to mod.  
xyln, cherty & slightly sand, thin  
strks poor vuggy por. No sat. No odor.