

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

16-23-22W

COMPANY MC CLURE OIL CO.


SEC. 16 T. 23 R. 22W
LOC. C SE SW

FARM Rumford, Ina K. NO. 1

TOTAL DEPTH 4615'
COMM. 8-1-66 COMP. 8-13-66
SHOT OR TREATED
CONTRACTOR Leben Drlg, Inc.
ISSUED 11-5-66

COUNTY Hodgeman

KANSAS



CASING

20	10	
15	8 5/8	287.30' w.235 sx cem.
12	6	
13	5	

ELEVATION 2308' K.B.

PRODUCTION DRY

FIGURES INDICATE BOTTOM OF FORMATIONS

0	730	Shale, Redbed
730	1416	Redbed, Shale
1416	1456	Anhydrite
1456	1478	Shale
1478	2350	Shale, Shells
2350	2550	Shale
2550	3082	Lime
3082	3460	Lime, Shale
3460	3585	Lime, Shale, Chalky Streaks
3585	3790	Lime, Shale
3790	3900	Lime, Shale, Chalky Streaks
3900	4568	Lime
4568	4615	Lime, Chert
	<u>4615</u>	<u>RTD - D. & A.</u>

My Commission Expires: April 1, 1967

TOPS: SCOUT

30' with 235 sacks Posmix,

Anhydrite 1415

Heebner 3877

Lansing 3953

Marmaton 4257

Cherokee 4468

Mississippi Warsaw 4554

Mississippi Osage 4579

at the above and foregoing is
the Rumford #1 well, located
in Range 22 West, Hodgeman
County, Kansas. Records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in
and for Barton County, Kansas, this 16th day of August, 1966.