

25-23-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.
Farm- Koontz No. 1

SEC. 25 T. 23 R. 22W
NE NW NE

Total Depth. 4633'
Comm. 6-4-61 Comp. 6-18-61
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 8-26-61

County Hodgeman
KANSAS



CASING:

8 5/8" 213' cem w/175 sx.

Elevation. 2256' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale, sand & shells	213
shale & shells	225
shale, sand & shells	1360
Anhydrite	1410
shale & shells	2360
shale, shells & lime	2525
shale & lime	3987
lime	4030
lime & shale	4068
lime	4120
lime & shale	4212
lime	4275
lime & shale	4365
lime	4410
lime & shale	4510
lime	4633 RTD
Total Depth	

TOPS: SAMPLE

Heebner	3860
Brown Lime	3941
Lansing	3955
Marmaton	4240
Cherokee Shale	4462
Conglomerate	4528
Mississippi (Warsaw)	4571
Mississippi (Osage)	4606

DST #1 4511-65', op 30 mins, rec. 10' drilling
mud. IBHP 200#, FBHP 0#/20 mins.

DST #2 4569-4633' Packer failure.

DST #3 4580-4633', op 1 hr, rec. 1200'
salt water. IBHP 1475#, IFP 185#, FFP 560#,
FBHP 1460#/20 mins.