

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


36-23-22W

Company- THE ATLANTIC REFINING CO.
Farm- Ross E. Hall No. 2

SEC. 36 T. 23 R. 22W
C NE SE

Total Depth. 4595
Comm. 1-25-56 Comp. 2-12-56 ✓
Shot or Treated.
Contractor. Lewis Drilling Co.
Issued. 5-5-56

County Hodgeman
KANSAS



CASING:

8 5/8 @ 253.92' w/ 200 sx cmt.
5 1/2 @ 4591' w/ 300 sx cmt.

Elevation. 2286 DF

Production. 218 BOPD

Figures indicate Bottom of Formations.

sand & post rock	50
sand	200
shale & shells	730
anhydrite	755
red bed	800
sand	970
shale & lime	3950
lime	4451
lime & shale	4485
lime	4555
lime & chert	4595
Total Depth	

TOPS:	
Heebner	3846
Toronto	3878
Douglas	3901
Brown lime	3931
Lansing	3943
Marmaton	4235
Cherokee	4449
Conglomer ate	4516
Mississippian	4558

Perf. 4 SPF/4478-86 (SJM) Cherokee
prod. 83.25 pumping/24 hrs.
Perf. 4334-44 w/ 4 JSPF (SJM) sqzd off
Perf. 4 JSPF/4349-55 SJM Marmaton
no test