

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


36-23-22W

Company- ATLANTIC REFG. CO.
Farm- Ross E. Hall No. 3

SEC. 36 T. 23 R.22W
C SE SE

Total Depth. 4551'
Comm. 12-13-56 Comp. 12-31-56
Shot or Treated.
Contractor. Graham-Michaelis Drlg. Co.
Issued. 8-17-57

County Hodgeman
KANSAS



Elevation. 2301' DF

Production. Phy. Pot. 28 B.

CASING:

8 5/8" 242.15' w/200 sx cem.
5 1/2" 4538.15' w/300 sx cem.

Figures indicate Bottom of Formations.

shale	265
sand	296
shale	570
sand	600
shale-sand	845
sand	970
shale-sand	1190
shale-shells	1375
Anhydrite	1395
shale-shells	1680
lime-shale	2280
shale-brkn lime	2440
lime-shale	3963
lime	4383
lime-chert	4422
chert-lime	4450
lime-cherty	4505
lime	4551
Total Depth	

TOPS:

Heebner	3853
Brown lime	3943
Lansing-Kansas City	3952
Marmaton	4246
Ft. Scott	4422
Cherokee	4459
Conglomerate-shale	4515
Conglomerate -cherty	4538

DST #1 - 4326-51' Open 1 hr.
Rec. 45' slightly oil & GCM.
170' heavily oil & GCM. IBHP
940#/30 min. FBHP 760#/30 min.
IF 40#, FF 75#.

DST #2 - 4354-80' Open 1 hr.
Rec. 17' mud. IBHP 0#/30 min.
RBHP 0#/30 min. IF 0#. FF 0#.

DST #3 - 4478-4505' Open 1 hr.
Rec. 10' mud. IBHP 25#/30 min.
FBHP 38#/30 min. IF 12#, FF 15#.

DST #4 - 4515-51' Open 1 hr.
Rec. 25' mud. IBHP 5#/30 min.
FBHP 40#/30 min. IF 5#, FF 10#.

Perfs. 4324-55' (Sci.lumberger
Meas.)

Produced 38 BOPD, 25.42 EWPD in 24
hrs., pmp. @ 14 - 34" SPM