

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


36-23-22W

Company- ATLANTIC REFG.
Farm- Lois Miller No. 2

SEC. 36 T. 23 R. 22W
C SW NE

Total Depth. 4560'
Comm. 6-15-56 Comp. 6-30-56
Shot or Treated.
Contractor. Lewis Drlg. Co.
Issued. 11-10-56

County Hodgeman
KANSAS



CASING:
8 5/8" 250.07' w/200 sx cem.
5 1/2" 4550.75' w/300 sx cem.

Elevation. 2262' DF

Production. State Test 93.52 BO-
26.38 BW

Figures Indicate Bottom of Formations

clay-shale	250
shale	720
Anhydrite	740
shale-shells	1360
shale-lime	1725
shale-shells	2040
lime-shale	3630
lime	3640
lime-shale	3810
lime	3860
lime-shale	3970
lime	4560
Total Depth	

TOPS: Scout	
Heebner	3817
Brown lime	3899
Lansing	3911
Marmaton	4207
Cherokee shale	4321
Conglomerate	4485
Mississippi	4504

DST #1 - 4292-4337': Open 1 hr.,
rec. 640' blk foamy gassy oil
cut w/mud @ top & filtrate wtr.
@ btm. IFP 100#, FFP 300#. No
BHSIP(tool failed, questionable
reading).

DST #2- 4439-4460': Open 1 hr.,
rec. 20' drilling mud. IFP 4#,
FFP 6#, BHSIP 30# in 15 min.

Perf.: 4293-4300' and 4324-31'
(Schlumberger Meas.) w/4 jet
shots per foot, Marmaton for-
mation.