


Company- TEXACO, INC.
Farm- E. F. Lippoldt

No. 1

SEC. 14 T. 23 R. 23W
C SE NW
3250' WEL & 2030' SNL

14-23-23W
County Hodgeman

KANSAS



Total Depth. 5231' PBD 4647'
Comm. 2-22-63 Comp. 3-24-63
Shot or Treated.
Contractor. Sierra Pet., Inc.
Issued. 8-17-63

CASING:

8 5/8" 514' cem w/300 sx.
5 1/2" 5123' cem w/200 sx.

Elevation. 2292' DF

Production. 74 BOPD, NW

Figures Indicate Bottom of Formations.

surface clay & sand	150
shale & shells	505
medium hard shale (blue)	515
shale	530
red bed	799
anhydrite	810
red bed	910
sand	1070
red bed & shale	1412
anhydrite	1440
shale	1465
shale & shells	2180
lime & shale	2666
lime	2693
lime & shale	3555
lime	3981
lime (hard)	4015
lime	4476
conglomerate	4506
lime	4513
Mississippi lime	4530
Mississippi	4540
chert	4660
chert & lime	4694
lime	4768
lime & sand	4810
lime	5228
granite	5231
Total Depth	

PLUG BACK TOTAL DEPTH 4647'

TOPS: LOG

Blaine	793	
Anhydrite	1410	- 1427
Elmont	3246	
Heebner	3808	
Lansing	3874	
Marmaton	4288	
Fort Scott	4402	
Mississippi Warsaw	4488	
Osage	4536	
Kinderhook	4658	
Viola	4788	
Simpson	4924	
Arbuckle	4970	
Granite	5230	

LOGS RUN: Laterolog, Amplitude Sonic,
Integrated Sonic & 15 Velocity Surveys.