

1- 23 - 23W

~~WELL LOG BUREAU - KANSAS~~
508 East Murdock, Wichita, Kansas

Company- BEARDMORE DRLG.
Farm- Clifton

No. 4

SEC. 1 T. 23 R. 23W
217' SW of NE NE

Total Depth. 4503

Comm. 12-3-65


Comp. 12-16-65

Shot or Treated.

Contractor. Gabbert-Jones

Issued. 4-16-66

County Hodgeman
KANSAS



CASING:

8 5/8" 1364' w/600 sx.
5 1/2" 4473' w/75 sx.

Elevation. ~~2211 LKB~~

Production. SWDW

Figures Indicate Bottom of Formations.

shale & shells	481
Anhydrite	502
shale, gyp, sand	760
shale & shells	814
sand	1002
shale	1153
shale & redbed	1348
Anhydrite	1365
"	1390
sand & shale	1705
shale	2125
shale & lime	3807
lime	4375
lime & shale	4437
core	4473
lime & chert	4503
Total Depth	

SAMPLE TOPS:

Blaine	724
Base Blaine	740
Anhydrite	1348
Stone Corral	1354
Heebner	3746
Lansing	3807
Base Kansas City	4176
Fort Scott	4346
Cherokee Shale	4371
Mississippi Warsaw	4434
Mississippi Osage	4472

DST:

CORES:

#1 4351-4375
#2 4471-4503

#1 4437-4451
#2 4451-4458