

State Geological Survey

KANSAS DRILLERS LOG

WICHITA, BRANCH


API No. 15 — 083 — 20,356
County Number

S. 13 T. 23 R. 23 ^RW

Loc. C SW SW NW

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2326'

DF 2332' KB 2334'

Operator

Texaco, Inc.

Address Box 2420

Tulsa, Oklahoma

Well No.

#6

Lease Name

E. F. Lippoldt "B"

Footage Location

330 feet from (N) (S) line

330 feet from (E) (W) line

Principal Contractor

DaMac

Geologist

Larry Rogers

Spud Date

3/6/74

Total Depth

4590'

P.B.T.D.

4589'

Date Completed

3/29/74

Oil Purchaser

Skelly

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surf pipe	12 1/4"	8-5/8"	24#	507'	poz	385	2% CaCl.
Production	7-7/8"	5 1/2"	14#	4590'	poz	200,18%	salt, CFR-2
					Lite wate	240	
(500 sx thru DV tool @ 2280')							

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	jets	4578-88'
TUBING RECORD			2	jets	4555-76'
Size	Setting depth	Packer set at			
2-3/8"	4571'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 15% NEA	4555-88'

INITIAL PRODUCTION

Date of first production 3/24/74 (Swab test)		Producing method (flowing, pumping, gas lift, etc.) Pmpg			
RATE OF PRODUCTION PER 24 HOURS	Oil 74 bbls.	Gas -0- MCF	Water 3 BSW bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 4555-4588'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator TEXACO INC.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL
Well No. 6	Lease Name E. F. Lippoldt "B"	
S 13 T 23 S R 23 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sd & Sh	0	507	FDC	3100-4588'
Sh & Shells	507	845	Laterolog	surf-4589'
Stone correl	845	858		
Sh & Red Bed	858	1345		
Anhydrite	1345	1460		
Sh & Shells	1460	1492		
Li & Sh	1492	2260		
Li	2260	4140		
Li	4140	4590		
TD	4590			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received 	<i>F. E. Anderson</i> F. E. ANDERSON Signature
	Operations Superintendent Title
	May 29, 1974 Date

WELL LOG

13-23-23W

API# 15-083-20, 356

COMPANY

Texaco

SEC. 13 T. 238 R. 23W

FARM

E. F. Lippoldt

NO. "B" 6

LOC. SW SW NW

TOTAL DEPTH

4590'

COUNTY Hodgeman, Kansas

COMM.

2-28-74

COMP.

3-16-74


CONTRACTOR

DaMac Drilling Company, Inc.

CASING

8 5/8" @ 507' w/385 ex.

3 1/2" @ 4606' w/500 ex.



ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

507' Sand & Shale
845' Shale & Shells
858' Stone corral
1345' Shale & Red Bed
1460' Anhydrite
1492' Shale & Shells
2260' Lime & Shale
4140' Lime
4590' Lime
4590' RTD