

## WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

14-23-23W

Company- TEXACO, INC.

Farm- Lippoldt

No. 2

SEC. 14 T. 23 R. 23W  
C SE NE


Total Depth. 4650'

Comm. 4-21-63 Comp. 5-6-63

Shot or Treated.

Contractor. Sholom Drilling Co., Inc.

Issued. 8-10-63

County Hodgeman  
KANSAS

## CASING:

8 5/8" 524' cem w/310 sx.

4 1/2" 4650' cem w/100 sx.

Elevation. 2319' DE

Production. 39 BOPD, NW

## Figures Indicate Bottom of Formations.

|                     |          |
|---------------------|----------|
| clay & post rock    | 50       |
| blue shale & shells | 525      |
| shale & shells      | 835      |
| Anhydrite           | 850      |
| red bed             | 920      |
| sand                | 1175     |
| red bed & sand      | 1443     |
| Anhydrite           | 1479     |
| shale & shells      | 1755     |
| blue shale & redbed | 2010     |
| shale & shells      | 2225     |
| lime & shale        | 2995     |
| shale               | 3031     |
| lime & shale        | 4121     |
| lime                | 4205     |
| lime & shale        | 4243     |
| lime                | 4311     |
| lime & shale        | 4420     |
| lime                | 4525     |
| lime                | 4650 RTD |
| Total Depth         |          |

## TOPS: LOG

|             |      |
|-------------|------|
| Heebner     | 3858 |
| Toronto     | 3870 |
| Lansing     | 3922 |
| Marmaton    | 4342 |
| Ft. Scott   | 4458 |
| Mississippi | 4544 |
| Osage       | 4604 |