

33-23-23


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JONES-GEBERT OIL CO.
Farm- Cole No.1

SEC. 33 T. 23 R. 23W
C NE SW

Total Depth. 4772'
Comm. 3-16-63 Comp. 3-30-63
Shot or Treated.
Contractor.
Issued. 7-6-63

County Hodgeman
KANSAS



CASING:
8 5/8" 295' cem w/200 sx.

Elevation. 2426' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	295
red bed-blue clay-shale	695
red bed & shale	1345
shale	1580
Anhydrite	1770
shale w/lime strks.	2205
shale w/lime strks.	2455
lime & shale	2700
Ft. Riley Lime	2765
lime	2960
lime & shale	3330
shale & chalk & lime	3514
shale w/chalk & lime strks.	3796
shale, shale, & lime	3950
shale	4043
Kansas City Lime ?	4078
Kansas City Lime	4203
lime & chert stringers	4233
lime & chert	4316
Kansas City Lime	4474
lime & shale	4500
lime w/shale	4542
lime & shale	4611
lime w/shale	4640
lime, shale & chert	4686
lime & chert	4700
Miss. lime, chert, Dolomite	4707
Mississippi	4769
R.T.D. Wire Line	4772
Total Depth	

TOPS: SAMPLES

Anhydrite	1575
Topeka	3680
Heebner	3973
Toronto	3992
Lansing	4038
Base Kansas City	4449
Cherokee	4590
Conglomerate	4669
Mississippi Sparg	4692
Mississippi Warsaw	4702