

15-083-20475

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.


API No. 15 — 083 — 20,478
County Number

S. 35 T. 23 R. 23 E
W

Loc. C NW SW

County Hodgeman

640 Acres



Locate well correctly

Elev.: Gr. 2413

DF 2420 KB 2422

Operator
Dunne-Gardner & Sotex Company, Inc.

Address
Suite 250, 200 West Douglas Wichita, Kansas 67202

Well No. #1 Lease Name Whiteside

Footage Location
660 feet from (N) line 660 feet from (W) line

Principal Contractor Dunne-Gardner Petroleum, Inc. Geologist George N. Mueller

Spud Date August 26, 1976 Total Depth 4750 P.B.T.D.

Date Completed September 7, 1976 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	329'	Common	250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Dunne-Gardner Petroleum, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry hole

Well No. 1 Lease Name Whiteside

S 35 T 23 R 23 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	0	328	Anhydrite	1570
Sand and red clay	328	782	Base Anhydrite	
Red bed	782	949	Heebner	3995
Blaine	949	967	Toronto	4009
Sand and shale	967	1570	Lansing	4068
Anhydrite	1570	1609	Base Kansas	
Shale and shells	1609	2442	City	4427
Lime and shale	2442	4076	Marmaton	4465
Lime	4076	4580	Fort Scott	4600
Shale and lime	4580	4630	Cherokee	4625
Lime	4630	4750	Mississippian	4685
DST #1, 4660-95, 30-30-30-30, very weak blow-13", Rec: 8' Mud NS, All pressures 0#			<u>ELECTRIC LOGS</u>	
DST #2, 4695-4707, 30-45-45-60, Very weak blow, Rec: 45' Gassy OCM (Free oil in tool) IFP 11-11#, FFP 21-21#, ISIP 106# FSIP 190#			Petro-Log Gr-n-GO & Caliper	
DST #3, 4707-25, 30-45-45-60, very weak blow-30", Rec: 25' mud wt, Salt water in tool, IFP 12-12#, FFP 47-47#, ISIP 1241# FSIP 1241#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Vice-President

Title

September 2, 1977

Date

DRILLERS LOG

#1 WHITESIDE
C NW SW Section 35-23S-23W
Hodgeman County, Kansas

OPERATOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas 67202

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas 67202

COMMENCED: August 26, 1976

COMPLETED: September 7, 1976


CASING RECORD: 8-5/8" @ 329' w/250 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	328	Shale
328	782	Sand and red clay
782	949	Red bed
949	967	Blaine
967	1570	Sand and shale
1570	1609	Anhydrite
1609	2442	Shale and shells
2442	4076	Lime and shale
4076	4580	Lime
4580	4630	Shale and lime
4630	4750	Lime
4750		Rotary total depth

RECORDED
SEP 17 1976
COMMISSION EXPIRES
MARCH 1 1978


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct
log to the best of my knowledge and belief.


Don Gardner

Subscribed and sworn to before me this 14th day of September, 1976.

My commission expires:
March 1, 1978


Notary Public