

27-23-24W

Red

TYPE

★

AFFIDAVIT OF COMPLETION FORM
State Geological Survey
WICHITA, BRANCH

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5364 EXPIRATION DATE 6/30/83

OPERATOR Beren Corporation API NO. 15-083-20,979

ADDRESS 970 Fourth Financial Center COUNTY Hodgeman

Wichita, Kansas 67202 FIELD

** CONTACT PERSON Melvyn Abels PROD. FORMATION

PHONE (316) 265-3311

PURCHASER Central Crude Corporation LEASE Don "A"

ADDRESS 402 Commerce Plaza WELL NO. 3

Wichita, Kansas 67202 WELL LOCATION NW NE NE

DRILLING BEREDECO INC. 990 Ft. from east Line and

CONTRACTOR CONTRACTOR 330 Ft. from north Line of

ADDRESS 402 Commerce Plaza the NE (Qtr.) SEC 27 TWP 23S RGE 24W.

Wichita, Kansas 67202

PLUGGING NA WELL PLAT (Office Use Only)

CONTRACTOR CONTRACTOR

ADDRESS

TOTAL DEPTH 4736 PBTD

SPUD DATE 6/1/82 DATE COMPLETED 6/8/82

ELEV: GR 2462 DF KB 2474

DRILLED WITH (XXX) (ROTARY) (XXX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE CD-9811

Amount of surface pipe set and cemented 519' DV Tool Used? 1644'.


THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Don W. Beauchamp, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.



(Office Use Only)
KCC
KGS
SWD/REP
PLG.

Don W. Beauchamp

WHS-22-78
 SIDE TWO
 OPERATOR Beren Corporation

ACO-1 WELL HISTORY

LEASE Don "A" #3 SEC. 27 TWP. 23S RGE. 24W

FILL IN WELL INFORMATION AS REQUIRED: WELL NO.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime and shale	0	1475		
Red Bed and shale	1475	3160		
Lime and shale	3160	4535		
Lime and chert	4535	4729		
* RTD	4729			
*Drilled to 4736' with cable tools.				
DST #1 4664 - 4728 (Miss) 45/65/60/60 Stronb blow Rec: 550' GIP + 598' fluid (246' clean oil + 299' HOCM & mdy oil) 926/846 111/152 223/243				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated		
NA					
Date of first production 7/27/82	Producing method (flowing, pumping, gas lift, etc.) Pump		Gravity		
Estimated Production -I.P.	Oil 60 bbl.	Gas NA MCF	Water 25 %	20 bbls.	Gas-oil ratio NA CFPB
Disposition of gas (vented, used on lease or sold)			Perforations NA		

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or ~~Used~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	24#	534'	60-40 pozmix	350	3% CC
Production	7-7/8"	5 1/2"	14#	4728'	60-40 pozmix	200	10% salt, 3/4 of 1% CFR-2
DV Tool				1655'	HLC	400	
					Class "H"	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
NA			Open Hole		

TUBING RECORD

Size	Setting depth	Pecker set at