


15-083-21577

25-23s-24w



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Becker Oil Corp.**

P.O. Box 1159
Ponca City, OK 74602

ATTN: Clyde Becker

25-23-24 Hodgeman KS

Schauvillege #1

Start Date: 2008.11.19 @ 02:32:46

End Date: 2008.11.19 @ 12:19:16

Job Ticket #: 33547 DST #: 1

Trilobite Testing, Inc

PO Box 1733 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Becker Oil Corp.

P.O. Box 1159
Ponca City, OK 74602

ATTN: Clyde Becker

Schauvilliege #1

25-23-24 Hodgeman KS

Job Ticket: 33547

DST#: 1

Test Start: 2008.11.19 @ 02:32:46

GENERAL INFORMATION:

Formation: **Cher Snd**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 04:46:46

Time Test Ended: 12:19:16

Interval: **4607.00 ft (KB) To 4655.00 ft (KB) (TVD)**

Total Depth: 4655.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Test Type: Conventional Bottom Hole

Tester: Kyle Kinderknecht

Unit No: 31

Reference Elevations: 2376.00 ft (KB)

2371.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8319

Inside

Press@RunDepth: 1402.21 psig @ 4614.00 ft (KB)

Start Date:

2008.11.19

End Date:

2008.11.19

Capacity: 7000.00 psig

Last Calib.: 2008.11.19

Start Time:

02:32:51


End Time:

12:19:16

Time On Btm: 2008.11.19 @ 04:45:16

Time Off Btm: 2008.11.19 @ 08:30:46

TEST COMMENT: IF BOB 35 sec
ISI 9"
FF BOB 30 sec
FSI 1" died to surface



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2339.33	106.27	Initial Hydro-static
2	580.22	107.38	Open To Flow (1)
29	1161.35	128.10	Shut-In (1)
92	1415.47	125.01	End Shut-In (1)
93	1195.03	124.78	Open To Flow (2)
138	1402.21	127.28	Shut-In (2)
225	1421.16	125.26	End Shut-In (2)
226	2215.18	125.76	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
3750.00	Gsy Free Oil Reversed Out	50.89
0.00	180' GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Becker Oil Corp.

P.O. Box 1159
Ponca City, OK 74602

ATTN: Clyde Becker

Schauvilliege #1

25-23-24 Hodgeman KS

Job Ticket: 33547

DST#: 1

Test Start: 2008.11.19 @ 02:32:46

Tool Information

Drill Pipe:	Length: 4365.00 ft	Diameter: 3.82 inches	Volume: 61.88 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 245.00 ft	Diameter: 2.25 inches	Volume: 1.20 bbl	Weight to Pull Loose:	80000.00 lb
		Total Volume:	63.08 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	30.00 ft			String Weight: Initial	63000.00 lb
Depth to Top Packer:	4607.00 ft			Final	77000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	48.00 ft				
Tool Length:	75.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		
Tool Comments:					

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
------------------	-------------	------------	----------	------------	----------------

Change Over Sub	1.00			4581.00	
Shut In Tool	5.00			4586.00	
Hydraulic tool	5.00			4591.00	
Jars	4.00			4595.00	
Safety Joint	3.00			4598.00	
Packer	4.00			4602.00	27.00 Bottom Of Top Packer
Packer	5.00			4607.00	
Stubb	1.00			4608.00	
Perforations	5.00			4613.00	
Change Over Sub	1.00			4614.00	
Recorder	0.00	8319	Inside	4614.00	
Recorder	0.00	8369	Inside	4614.00	
Blank Spacing	32.00			4646.00	
Change Over Sub	1.00			4647.00	
Perforations	5.00			4652.00	
Bullnose	3.00			4655.00	48.00 Bottom Packers & Anchor
Total Tool Length:	75.00				



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Becker Oil Corp.

Schauvillege #1

P.O. Box 1159
Ponca City, OK 74602

25-23-24 Hodgeman KS

Job Ticket: 33547

DST#: 1

ATTN: Clyde Becker

Test Start: 2008.11.19 @ 02:32:46

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API: 37 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity: ppm

Viscosity: 42.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.59 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3200.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
3750.00	Gsy Free Oil Reversed Out	50.890
0.00	180' GIP	0.000

Total Length: 3750.00 ft

Total Volume: 50.890 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time

