

15-055-21892

32-23s-29w

Steven P. Murphy, PG
American Warrior, Inc.
P.O. Box 399
Garden City, KS 67846

GEOLOGICAL REPORT

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2006
CONSERVATION DIVISION
WICHITA, KS

AMERICAN WARRIOR, INC.

Maxwell #1-32
390' FSL & 370' FEL
Section 32-T23S-R29W
Finney County, Kansas
15-055-21892

OPERATOR: AMERICAN WARRIOR, INC.

WELL: MAXWELL #1-32

API NUMBER: 15-055-21892-00-00

LOCATION: 390' FSL & 370' FEL
32-T23S-R29W
FINNEY COUNTY, KANSAS

WELLSITE: WHEAT STUBBLE

COMMENCED: NOVEMBER 13, 2005

COMPLETED: NOVEMBER 17, 2005

ELEVATIONS: 2780' G.L. 2786' K.B.

TOTAL DEPTH: 4875' (DRILLER) 4879' (LOG)

CASING: SURFACE: 8 5/8" @ 461'
PRODUCTION: D&A

SAMPLES: 10' FROM 3850' TO TD

DRILL STEM TESTS: NONE

LOGS COMPENSATED NEUTRON DENSITY,
SONIC, MICROLOG, & DUAL
INDUCTION BY LOG-TECH

DRILLING CONTRACTOR: CHEYENNE DRILLING RIG 11

REMARKS: GEOLOGICAL SUPERVISION FROM
3800' TO T.D.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2006
CONSERVATION DIVISION
WICHITA, KS

FORMATION TOPS	LOG
Anhydrite	1917 (+869)
Heebner	4018 (-1232)
Lansing	4068 (-1282)
Stark	4429 (-1643)
BKC	4512 (-1726)
Marmaton	4528 (-1742)
Pawnee	4612 (-1826)
Cherokee	4654 (-1868)
Morrow Sand	None
Miss. St. Gen.	4777 (-1991)


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2006
CONSERVATION DIVISION
WICHITA, KS

SUMMARY AND RECOMMENDATIONS

Structurally, the Maxwell #1-32 ran low to the nearest producing well, the Obrate #1-5 on all horizons. The Morrow Sand was absent in this well.

Based on the results of sample & log analysis, it was recommended and agreed that this test be plugged and abandoned.

Respectfully submitted,


Steven P. Murphy, P.G.
Kansas Licensed Geologist (#228)

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2006
CONSERVATION DIVISION
WICHITA, KS