


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
J. Bott No. 1.

SEC. 7 T. 23 R. 3W.
CWL SW NW
660' N 330' E of W $\frac{1}{4}$ cor.

Total Depth. 3426'6"
Comm. 3-4-38 Comp. 3-27-38
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 6-18-38

County Harvey.



CASING.

103/4" 526' 7" 3426'6" "

Elevation.

Production. Pot. 205 B.

Figures Indicate Bottom of Formations.

collar	15
clay and sand	145
shale and shells and sandstone	360
shale blue and sand shells	485
shale and shells	530
broken lime and gyp	620
shale and shells	635
anhydrite	670
shale and shells	780
broken lime and shale	855
broken lime	900
sand	930
lime broken	945
shale and shells	1020
lime and broken lime	1055
broken lime	1082
sand	1091
shale and shells	1150
broken lime sdy	1240
shale and lime	1300
broken lime	1335
shale and shells	1610
lime broken	1645
shale and shells	1695
broken lime	1720
shale and shells	1860
broken lime and shale	1920
shale and shells	2070
sdv shale	2090
broken lime and shale	2340
shale and lime shells	2410
lime	2440
sand and shale	2515
shale and shells	2555
lime broken	2595
lime	2815
lime and shale	2860
lime broken cherty	2895

lime and shale	2925
lime	2970
lime and shale broken	2997
lime	3135
shale and lime	3210
shale	3225
shale green	3265
shale grey & yellow	3297'6"
chat	3426'6"

Total Depth.

Gas show 3290-95; 3310-15; 3320-25; 3345-50 and 3358-63

Oil show 3365-75; 3380-90; 3395-3403

Prod. 1st 24 hours 205 oil.
shot 38 holes in 7 " from 3363-3375

chat 3297-6 -3426'6