


CARL HIPPLE OIL CO.
 Martindell No. 3.

SEC. 18 T. 23 R. 3W
 NEo SE

Total Depth. 3367'
 Comm. 10-28-39 Comp. 12-15-39
 Shot or Treated.
 Contractor.
 Issued. 1-20-40

County. Harvey



CASING:
 10" 285'10"
 7" 3305'

Elevation.

Production. Pot. 150 B.

Figures Indicate Bottom of Formations.

shale & sand	285	chat sft, inc in oil	3343
shale	543	lime hrd	3351
shale & lime	675	chat sft, inc in oil	
shale & lime shells	837	& gas	3360
sand & lime	914	chat sft	3361½
no log	1020	lime & chat fine med	3362
brkn lime & shale	1100	chat & lime, coarse sft,	
shale & lime	1157	shows oil	3367
sand & lime	1180	Total Depth.	
shale	1286		
shale & lime shells	1345		
shale	1500		
shale & lime shells	1695		
shale & lime	1780		
shale	1930		
shale & lime	1985		
lime	2022		
brkn lime & shale	2070		
shale & lime	2140		
shale	2180		
shale & lime shells	2220		
shale	2321		
shale & shells	2470		
shale & lime	2562		
shale	2568		
lime	2592		
shale	2602		
shale & lime	2630		
lime	2860		
hrd shale & lime	2890		
shale & lime	2918		
lime	2966		
shale & lime	3035		
brkn shale & lime	3070		
shale	3102		
shale & lime	3132		
shale brkn	3150		
shale	3244		
shale & shells	3253		
chat & lime	3257		
shale	3260		
sdv lime sft	3276		
lime hrd	3277		
lime sft	3283		
lime hrd	3288		
chert	3295		
chat	3296		
shale	3298		
chat	3300		
lime	3303		
lime, changed to cable			
tools	3305		
lime & chat hrd	3316		
lime & chat hrd, trace			
of oil	3324		
lime & chat hrd	3332		
lime shells hrd	3333		
lime & chat sft, sh oil			
& gas	3338		