


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

BENNETT & WILHELM
Cunningham No. 1.

SEC. 19 T. 23 R. 3W
CNE SE

Total Depth. 3369'
Comm. 1-22-38 Comp. 2-26-38
Shot or Treated. 2000 Gals.
Contractor.
Issued. 5-28-38

County. Harvey



CASING:
12 $\frac{1}{2}$ " 252'

Elevation.

Production. Pot. 846 B.

Figures Indicate Bottom of Formations.

sand	140	lime	2690
shale	282	brkn lime	2795
shale & lime	380	lime	2820
shale & shells	540	brkn lime	2900
shale & lime	630	shale	2910
lime	670	brkn lime	2925
shale & lime	960	lime	2932
lime & shells	1000	shale	2960
shale & shells	1135	lime	3105
shale & lime	1195	brkn lime	3150
shale & shells	1265	shale & lime	3190
shale	1330	shale	3245
lime	1339	shale & lime	3256
brkn lime	1370	chat	3369
shale & shells	1495	Total Depth.	
brkn lime	1515		
shale & shells	1525	Top Chat 3256	
shale & lime	1685	Sh gas 3287	
shale & shells	1805	Sh oil 3300	
shale	1820	Gas increase 3320	
brkn lime	1840	Sh wtr 3330	
shale	1845	Increase in oil 3338-3341	
shale & lime	2000	1st free oil 3345-3350	
shale	2005	Increase oil 3350-3354	
lime	2034	Gradual inc. oil 3354-3360 $\frac{1}{2}$	
shale	2045	Oil start filling hole 3360 $\frac{1}{2}$ -3367	
lime	2060	Shut down over night 700' oil	
shale & shells	2120	in hole	
shale	2148	Drilled 2'	
brkn lime	2160	Fluid raised from 700 to 1400	
shale	2165		
shale & lime	2200	Pumping well.	
shale	2280		
shale & lime	2315		
lime	2335		
shale & lime	2345		
brkn lime	2410		
shale rotten	2480		
lime & shale	2575		