


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CLAUDE WENTWORTH - SHELL OIL CO., INC.
A.M. Day No. 2.

SEC. 19 T. 23 R. 3W
CNL NE NW
330' fr NL 660' fr EL NW $\frac{1}{4}$

Total Depth. 3367'
Comm. 1-8-41 Comp. 2-27-41
Shot or Treated. 1000 Gals. 3361-65 2-6-41
Contractor. Claude Wentworth
Issued. 3-22-41 Rotary O-3311
Cable 3311-67

County. Harvey



CASING:
10 $\frac{3}{4}$ " 263' Com.
5 $\frac{1}{2}$ " 3300' Com.

Elevation.

Production. Pot. 264 B.

150 BW

Figures Indicate Bottom of Formations.

clay, sand, shale	220
sand & shalo	263
shale & lime	471
shale & shells	635
shale & lime shells	958
shale & shells	1030
lime	1200
shalo & lime	1255
lime	1355
shalo	1440
shale brkn	1615
shalo & shells	1900
shale & lime	2173
shale & shells	2200
lime	2280
lime hrd	2290
lime brkn	2438
shale & lime	2506
lime	2600
lime brkn	2693
lime & shale brks	2760
lime brkn	2806
lime	2908
lime brkn	3022
slate gy & shale	3080
lime	3137
shale & shells	3190
shale	3230
lime	3242
slate	3246
shale & lime	3294
3294 equals 3284 SLC	
chat	3284-3323
3323 equals 3319 SLC	
chat	3319-3367
Total Depth.	

Top Mississippi chat 3275
Corrected

1st sh oil 3337
sh gas 3317
oil pay 3361-65
filled up 1800' w/oil after
acidizing. Well would not
flow

Established potential of
264 bbls oil & 150 BW in
24 hrs based on an 8-hr
pump gauge of 88 BO, 50 BW