

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG WICHITA, KANSAS

Location C SW SW Sec. 19 T. 23 R. 3W.  
660' WL 660' SL SW  $\frac{1}{4}$

Casing Record. County. Harvey  
10" Farm. J.J. Krehbiel No. 1

20" 8  $\frac{1}{4}$ " 3280 Company. Olson Oil Co.--Shell.  
15  $\frac{1}{2}$ " 280 65/8" Contr. Olson Drlg Co.  
12  $\frac{1}{2}$ " 53/16" Comm. 5-11-32 Comp. 6-29-32  
Total Depth. 3373 Shot Quarts Between.



Correspondence Regarding This Well Should Be Referred To.

Elevation

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 7-23-32.

Flow 280 bbls 22 hours

Electric Rotary 3286 and Cable  
tools 3286 to 3373.

Formation Depth

sand	160
shale	240
shale and shells	345
sand	450
shale and shells	580
lime	630
lime broken	726
shale and shells	1300
sand broken	1365
shale and shells	1550
shale	1740
sticky shale	1811
shale	2147
shale and shells	2192
shale	2281
shale and shells	2408
lime	2418
broken lime	2423
lime	2430
sand	2517
sdv shale	2550
lime	2560
shale	2582
shale	2595
lime	2653
shale sdv	2805
lime	2912
shale sdv	2984
shale	3009
shale sdv and shells	3055
sand	3070
shale	3188
shale	3220
V.C. shale	3274
chat	3290
3290 equal 3286 S.L.C.	
Top chat	3269
lime	3299
lime hard show gas	3307
lime increase gas	3314
lime Increase oil	3329
lime	3337
chat	3360
chat spraying oil.	3373

estimated 1 M. gas and 2 and 3  
barrels oil per hr flow 3340

TD.

Flow 280 bbls 22 hours.

ending 2 P.M. 6-29-32

Flow thru casing no pressure available.