

DERBY OIL CO.
Jerome No. 1.

SEC. 30 T. 23 R. 3W
SW¹/₄ NE
247' fr SL 330' fr WL NE¹/₄

Total Depth. 3359'
Comm. 9-12-37 Comp. 10-29-37
Shot or Treated. 2000 & 2000 Gals.
Contractor. Rose Spring Drlg. Co.
Issued. 11-27-37

County. Harvey



CASING:
12¹/₂" 248'
53/16" 3264'

Elevation.

Production. Pot. 461 B.

Figures Indicate Bottom of Formations.

sand	100	Est. gas 3319-30 200,000 ft.
sand & clay	200	lime brown 3334
shale & red rock	249	Showing oil & more gas
shale-lime shells	310	Hole filled 700' oil 17 hrs.
shale & lime	490	lime mod hrd 3337
brkn lime & gyp	645	2 BW 2 hrs.
lime & shale	740	lime mod sft 3352
brkn lime	880	No increase in oil or gas,
shale & shells	915	Swabbed every hour.
shale & lime	940	Made 15 Bbls oil swabbing down
brkn lime	1110	Made 3 Bbls oil per hr and 4
shale & shells	1260	BW in 8 hrs.
brkn lime	1305	lime mod sft 3359
shale	?	Total Depth.
shale & shells	1625	
shale & lime	1730	
shale & lime shells	1805	
shale & lime	1935	Acidized 2000 Gals. Pot. 240 Bbls.
brkn lime	1990	flowing.
shale & lime	2100	Reacidized 2000 Gals. Pot. 461 Bbls.
sdv shale & lime	2125	flowing.
lime	2200	
brkn lime	2270	Top Lansing 2524
shale & lime	2300	Top Miss lime 3262
brkn lime	2425	Total Depth 3359 in Miss. lime.
sand	2475	
brkn lime	2560	
lime & shale	2605	
lime	2750	
brkn lime	2800	
lime	2869	
lime	3040	
shale & lime	3182	
shale	3225	
shale & lime	3265	
Top Miss lime	3262	
chat	3269	
Standardized		
Bailed hole dry		
Top Cement in casing	3245	
Drilled thru plug at	3263	
lime hrd	3273	
lime mod sft	3276	
lime wh hrd	3286	
red rock	3287	
lime hrd	3294	
lime mod sft	3294	
sm sh oil & gas	3390-94	
lime hrd	3310	
bailed hole dry		
lime hole crooked	3315	
lime wh hrd	3317	
lime wh hrd	3319	
chat mod sft	3330	