


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

T. P. HENRY
Devine No. 1.

SEC. 30 T. 23 R. 3W
SW NW SW NE
280' WL 780' SL

Total Depth. 3356'
Comm. 10-26-37 Comp. 2-5-38
Shot or Treated.
Contractor.
Issued. 10-15-38

County. Harvey



Rotary

CASING:

13" 256'
7" 3264'
53/16" 3265'

Elevation.

Production. Pot. 753 B.
10 BW

Figures Indicate Bottom of Formations.

shale	205
lime	1118
lime & shale	1344
shale & shells	1461
lime & shale	1658
shale	1722
lime & shale	1848
shale	1900
shale & shells	1944
shale	2010
lime	2228
shale & shells	2309
no log	2880
lime	3013
shale	3070
lime	3097
shale	3142
lime & shale	3173
shale	3228
shale varicolored	3252
lime & shale	3264
Top Chat 3264	
chat	3265
Cement 7" csg at 3264. Cement	
did not set. Recement. Rig up	
cable tools. Casing leaking.	
Plug back from 3237 (top of cem)	
to 3123 trying to shut off leak	
in csg. Drilled cement from	
3123 PB to 3265. Cement 53/16	
csg at 3265. Ripped 7" OD csg &	
recovered 2030'	
chat	3329
chat	3356
Total Depth.	

Acid treat with ? gals.