


OLSON-SHELL PETRO.
G.D. Nelson No. 2

SEC. 30 T. 23 R. 3W.
NEc NW
330' NL 330' EL.

Total Depth. 3370
Comm. 6-13-35 Comp. 7-19-35.
Shot or Treated.
Contractor. Olson Drilling Co.
Issued. 8-3-35

County. Harvey.



CASING.

16" 237' 7" 3254'

Elevation.

Figures Indicate Bottom of Formations.

Production. Pump 305 bbls
oil 50 BW 24 Hr.
Potential.

surface	12
sdv clay and shells	206
shale	237
shale and shells	480
broken lime	615
shale and shells	685
broken lime	823
broken lime & red rock	928
broken lime	1039
broken lime	1080
lime	1109
broken lime	1160
shale and shells	1270
shale	1580
lime	1680
shale and shells	1826
lime	1885
broken lime	1980
lime	2047
shale	2060
lime	2122
broken lime	2172
lime	2195
broken lime	2218
lime	2235
broken lime	2335
lime	2383
lime and shale	2428
lime	2437
broken lime	2515
lime	2535
shale	2553
broken lime	2602
lime	2719
shale	2742
lime	2767
shale	2778
lime	2817
2817 equals 2809 S.L.C.	
lime	2908
lime	2909
Oolitic lime	2915
lime	2979
shale	3133

lime	3156
shale and shells	3227
shale	3256
chat	3270
chat	3300
show oil and gas 3278	
chat and lime	3304
broken lime and shale	3305
increase oil and gas 3330 500' oil 4 Hr.	
chat	3315
lime	3336
increase oil and gas 3350-62	
chat.	3366
chat	3370
Total Depth.	