

OLSON - SHELL PETRO. CORP.
G.D. Nelson No. 6

SEC. 30 T. 23 R. 3W.
SE SE NW
330' fr E.L. 330' fr S.L.

Total Depth, 3360
Comm. 11-5-37 Comp. 12-12-37
Shot or Treated, 1000 gal.
Contractor, Olson Drlg. Co.
Issued, 1-15-38

County Harvey.



CASING.

13" 250'
7" 3294'
5½" 3310'

Elevation.

Production, Pot. 335 B.

Figures Indicate Bottom of Formations.

cellar	10
sand and shale	123
shale	180
shale and shells	250
shale and shells	503
broken lime	670
shale and shells	715
lime and shale	822
lime	857
broken lime	890
lime	930
broken lime and shale	972
lime	1009
lime	1194
shale and lime	1363
shale and shells	1396
broken lime	1415
shale and shells	1485
shale and shells	1595
broken lime and shale	1668
lime and shale	1800
shale	1836
lime	1865
lime and shale	1963
lime	2281
lime and shale	2435
sand and shale	2462
lime and shale	2486
lime	2515
shale and lime	2559
lime	2600
lime	2759
shale and broken lime	2792
lime	2904
sand and lime	2911
lime	2939
lime and shale	3005
3005 equals 3006 SLC	
lime and shale	3036
shale	3071
lime	3095
lime and shale	3180
shale	3278
chat	3294
chat	3360
Total Depth	Show oil 3315
	hole full oil 3352