


THE PALMER OIL CORP.  
Schrag No. 1.

SEC. 31 T. 23 R. 3W  
NW NE NW

Total Depth. 3368'  
Comm. 7-19-37 Comp. 8-15-37  
Shot or Treated.  
Contractor. Palmer Oil Corp.  
Issued. 9-11-37

County. Harvey



Elevation.

CASING:  
10" 264'  
6 5/8" 3264'5"  
2 1/2" tbg 3365'1"

Production. Pot. 804 B.

Figures Indicate Bottom of Formations.

sand & shells	180
shale & shells	450
brkn line	610
shale & shells	635
line	670
shale & shells	710
line brkn	940
line	1160
line brkn	1250
shale	1265
line	1305
line brkn	1625
shale & shells	1805
line brkn	1840
line	1870
line brkn	1880
line	1920
line brkn	2045
line	2110
shale & shells	2140
lime	2235
lime brkn	2300
lime	2405
shale & shells	2495
lime hrd	2610
lime	3205
lime & shale	3245
conglomerate	3260 ✓
chert little gas	3283
lime inc of gas	3284
sand G., sft	3290
chat sft	3305
chat hrd show of oil	3312
lime & chat	3330
little wtr 3344-49 & increase from 3349-3354	
chat	3354
sand G. sft	3356
sm sh oil 3349-54	
chat lgt sft 3 1/2 BWH	3360
chat hrd	3364
oil at 3360, inc at 3367	
chat sft	3367
chat firm	3368
Total Depth.	