

DAILY DRILLING REPORT

6-23-30W

4 #15-055-20,185

PROSPECT _____ YEAR 1975
 LEASE Haaq Estate "A" WELL NO. 1 WELL LOCATION C SW SE COUNTY Finney STATE Ks.
 DRILL SITE LEASE DESCRIPTION E/2 of Sec. 6-23-30W CODE _____
 OPERATOR Beren Corporation ELEVATION: GR 2862
 CONTRACTOR Abercrombie Drilling, Inc. DF _____
 GEOLOGIST Judd Hipps KB 2867
 DEVELOPMENT WELL PROSPECT TEST WELL ☒ NOTIFY _____
 OWNERSHIP _____
 IDENTIFICATION _____

TOPS	Anhydrite	2053	(+ 814)	Morrow	4758	(-1891)
	B. Anhydrite	2076	(+ 791)	Morrow Sand	4766	(-1899)
	Krider	2685	(+ 182)	St. Louis Porosity	4839	(-1972) -26'
	Heebner	3990	(-1123)			
	Toronto	4009	(-1142)			
	Lansing	4080	(-1213)			
	Marmaton	4517	(-1650)			
	Cherokee	4629	(-1762)			

MOVING IN & RIGGING UP May 15, 1975 SPUD May 16, 1975

SET 8-5/8 @ 361' w/ 200sx.

	DEPTH	DST
5/17/75	1075	
5/18/75	2390	
5/19/75	2705	#1 2652 - 2705 (Krider) 30/30/30/30 Fair blow Rec. 75' mud - No gas 138/112 43/86
5/20/75	3110'	
5/21/75	3609'	
5/22/75	3860	
5/23/75	4155	
5/24/75	4450	
5/25/75	4553	#2 4488 - 4553 Open one hour Rec. 5' mud 368/193 46/46
5/26/75	4758	#3 4725 - 4758 Open one hour Rec. 5' mud 18/18 9/18
5/27/75	4778	#4 4740 - 4778 Open one hour Rec. 10' SOCM 55/55 9/28
5/28/75	4830	
5/29/75	4882	#5 4814 - 4850 Open 1 hr 15 min Rec. 140' LM/show of tarry oil 946/928 9/92

5/30/75 4913 RTD D & A

ELECTRIC LOGS

Krider	2685	(+ 181)	St. Louis Porosity	4839	(-1972)
Heebner	3994	(-1127)			
Lansing	4082	(-1215)			
Marmaton	4506	(-1639)			
Cherokee	4626	(-1759)			
Morrow	4756	(-1889)			
Mississippi	4767	(-1900)			