

MAP NO. \_\_\_\_\_ ELEV. 2862 KB  
 STATE Kansas COUNTY Finney SEC. 5 Twp 23 S Rge 30 W  
 OPERATOR Pet-Ex Company LOC. C NW NW  
 WELL NO. 1 FARM NAME Boyd FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 OL WILDCAT (PD 4850) FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_  
 FR. 3-7-61 SPUD 3-8-61 COMP. 3-24-61 Texaco DHM

CONT./GEOL. Red Tiger rig # 1 Roger McCoy/Geol

|   |  |  |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|--|--|
| • |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |
|   |  |  |  |  |  |  |  |  |  |

| COMPLETION RECORD       |           |               |                  |
|-------------------------|-----------|---------------|------------------|
| NAME PRODUCING INTERVAL | FROM - TO | PERF. W/HOLES | TREATMENT RECORD |
| a                       |           |               |                  |
| b                       |           |               |                  |
| c                       |           |               |                  |
| d                       |           |               |                  |

a I. P. OIL/DIST. \_\_\_\_\_ WTR. \_\_\_\_\_ GAS \_\_\_\_\_ M.C.F.P.D. \_\_\_\_\_ CHK. \_\_\_\_\_ HRS. \_\_\_\_\_  
 b " " " " " " " "  
 c " " " " " " " "  
 d \_\_\_\_\_

D & A D & A

| SIP# | FI TP # | FI CP# | SIBHP |
|------|---------|--------|-------|
|      |         |        |       |

  

| GOR. | GR. | PBTD | TD          |
|------|-----|------|-------------|
|      |     |      | <u>4833</u> |

  

| CASING - CEMENT RECORD |            |
|------------------------|------------|
| SIZE                   | DEPTH      |
| <u>8-5/8"</u>          | <u>288</u> |
| W/SAX.                 | SIZE       |
| <u>225</u>             |            |

OPERATOR Pet-Ex Company WELL NO. 1 Boyd ELEV. 2862 KB

| SAMPLE TOPS | DEPTH | SUB SEA | ELEC. TOPS     | DEPTH       | SUB SEA    |
|-------------|-------|---------|----------------|-------------|------------|
| Heebner     | 3980  |         | Anhydrite      | 2018        |            |
| Toronto     | 3998  |         | Base Anhydrite | 2084        |            |
| Lansing     | 4032  |         | Krider         | 2680        |            |
|             |       |         | Winfield       | <u>2785</u> | <u>477</u> |
|             |       |         | Ft. Riley      | 2795        |            |
|             |       |         | Heebner        | 3983        |            |
|             |       |         | Toronto        | 3999        |            |
|             |       |         | Lansing        | 4031        | <u>477</u> |
|             |       |         | Marmaton       | 4490        | <u>477</u> |
|             |       |         | Cherokee       | 4608        |            |
|             |       |         | St. Louis      | 4728        | <u>477</u> |

Spud 3-8-61. 8-5/8" @ 288 w/225 sx. SO in Ft. Scott.  
 DST # 1 (Marm) 4579-4633, op 1 hr, wk blo, rec 40' drilling mud/  
 SSO, ISIP 1210/30 mins, FP 0-0, FSIP 200/30 mins. SO in  
 samples @ 4700.  
 DST # 2 (Miss) 4700-35, op 30 mins, rec 45' M w/spks of oil,  
 ISIP 895/30 mins, FP 0, FSIP 70/30 mins.  
 DST # 3 (Miss) 4795-4830, op 1 hr, rec 45' SO spkd mud, ISIP  
1265 1265/30 mins, FP 0-0, FSIP 1040/30 mins.  
 RTD 4830. logs (S i) to 4833. D & A COMPLETE 3-24-61

6/2309

LIBERAL ELECTRIC LOG TOPS

2862 KB

Winfield 2742 (+120)

Heebner 3986 (-1124)

Lansing 4028 (-1166)

Marmaton (Opr) 4490 (-1628) tst Mud + SSO

Miss 4726 (-1864) tst Mud + spks oil

TD 4833

D & A.