

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **DAVIDOR & DAVIDOR INC.**

SEC. 1 T. 23 N. 31W

LOC. C SW SE

FARM **Trekell**

NO. 1

TOTAL DEPTH **4794'**

COMM. **3-15-68**

COMP. **3-27-68**


SHOT OR TREATED

CONTRACTOR **Service DRlg.**

ISSUED **5-25-68**

COUNTY **Finney**

KANSAS



CASING

20	10	
15	8	5/8" 372' cem w/ 250 sk
12	6	
13	5	

ELEVATION **2867' GL**

PRODUCTION **DRY/ST. Gen**

FIGURES INDICATE BOTTOM OF FORMATIONS

3-15-68	0 -	300	Sand
	300 -	372	Shale
	372 -	1208	Shale & Salt
3-17-68	1208 -	1493	Shale
	1493 -	1855	Sand
	1855 -	2164	Sand, Shale & Anhydrite
3-18-68	2164 -	2539	Gypsum, Anhydrite & Shale
	2539 -	2716	Gypsum, Anhydrite & Shale
	2716 -	3023	Shale & Anhydrite
3-19-68	3023 -	3170	Shale & Anhydrite
	3170 -	3253	Lime & Anhydrite
	3253 -	3387	Lime & Shale
3-20-68	3387 -	3491	Lime & Shale
	3491 -	3602	Lime, Shale & Anhydrite
	3602 -	3785	Lime, Shale & Chalk
3-21-68	3785 -	3860	Lime, Shale & Chalk
	3860 -	4028	Shale, Chalk & Lime
	4028 -	4101	Lime & Shale
3-22-68	4101 -	4160	Lime & Chalk
	4160 -	4233	Shale & Lime
	4233 -	4314	Lime & Chalk
3-23-68	4314 -	4528	Lime & Chalk
3-24-68	4528 -	4709	Lime & Shale
3-25-68	4709 -	4794	Lime, Shale, & Sand

CASING RECORD

3-16-68

Ran 9 Jts. 8 5/8", 20# New Casing. Set @ 371 K.B.
 Cemented w/250 Sks. common, 2% C.C.

TOPS: LOG

Heebner	3980
Toronto	3998
Lansing Kansas City	4065
Marmaton	4504
Cherokee	4618
Morrow	4747
St. Genevieve	4767
WTD	4794

Plug hole, w/35 sks cement @ 700'
 30 sks cement @ 370'
 15 sks cement in top of hole