

A-7-44 52

MAP NO. 2895DF, 2887GL
 STATE Kansas COUNTY Finney SEC. 28 Twp 23S Rge 31W
 OPERATOR Sinclair(50%), Skelly(25%), Amerada(25%) LOC. App C NW/4
 WELL NO. 1 FARM NAME W. K. Rucker GU 1270 FT. FROM W LINE
 COL Hugoton (PD 2850) 1320 FT. FROM N LINE
 FR. 4-28-61 SPUD 5-27-61 COMP. 6-22-61 of NW/4

CONT./GEOL. Holm Drilling

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
 a. Herrington & 2649-84 124 500Ac, F/35X35

b. Krider

c. _____

d. _____

a I. P. OIL/DIST. _____ WTR. _____ GAS 285 M.C.F.P.D. _____ CHK. 25/64" HRS. 24

b. " " " " " "

c. " " " " " "

d. _____

SIP# _____ FI TP # 225 FI CP# 290 SIBHP _____ D & A ()

GOR. _____ GR. _____ PBDT 2735 TD 2774
 Casing - Cement Record

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>323</u>	<u>275</u>			
<u>4-1/2"</u>	<u>2773</u>	<u>150</u>			

OPERATOR Sinclair, Skelly, Amerada WELL NO. #1 W. K. Rucker GU ELEV. 2895 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Herrington	2649	+246			
Krider	2676	+219			
Winfield	2712	+183			

Spud 5-27-61. 8-5/8" @ 323 w/275 sx.

RTD 2774 in Perm Logs. 4-1/2" @ 2773 w/150 sx. CO to 2735.

P/32/(Krider) /2676-84, 250 Ac, Frac 15,000 gel Ac X 15,000# sd,
 Swb 90 BL/23 hrs, Ga 210 MCF / 5 BLPH/5 hrs, 3/4" ck, TP 25#,
 CP 250#. Ga 1,020 MCF/5 hrs, 3/4" ck, TP 75, CP 225.

P/92/(Herrington) /2649-72, 250 Mac, Frac 20,000 Ac X 20,000 sd.

Flod pt ld, Ga 150 MCF, FTP 10, FCP 25. Rec all ld.

IP CO Test, Ga 285 MCF/24 hrs, 25/64" ck, FTP 225, FCP 290.

From Herrington & Krider (2649-84).

COMPLETE 6-22-61.

C3 & el log.

Her 2626 + 271 > 285 MCF

Kri 2651 + 246

W 2710 + 187