

A-9-73

MAP NO. 2884 DF

ELEV. 2884 DF

STATE Kansas COUNTY Finney SEC. 8 Twp 23S Rge 31W

OPERATOR Apache Corporation - Tulsa, Okla. LOC. C SE/4


WELL NO. 1 FARM NAME Sherman Unit FT. FROM _____ LINE _____

OOL. Hugoton (PD 2800) FT. FROM _____ LINE _____

FR. 7-27-61 SPUD. 7-27-61 COMP. 8-28-61

CONT./GEOL. Sierra Drilling Co.

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Krider</u>	<u>2673-79</u>	<u>24</u>	<u>1000Ac, F/8x8</u>
b			
c			
d			



d I. P. OIL/DIST. _____ WTR. _____ GAS 1000 M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " " " "

c " " " " " " " "

d _____

D & A ()

SIP# 425 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD _____ TD 2690

CASING - CEMENT RECORD					
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>344</u>	<u>200</u>			
<u>4 1/2"</u>	<u>2689</u>	<u>175</u>			

OPERATOR Apache Corporation WELL NO. #1 Sherman Unit ELEV. 2884 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			<u>Krider</u>	<u>2673</u>	

Spud 7-27-61. 8 5/8" @ 344 w/200 sx.
 DST #1 (Permian) 2649-90, op 1 hr, GTS 10 mins, Ga 88 MCF/20 mins. Ga 108 MCF/60 mins, Rc 65' GCM, FP 30-30, SIP 445/30 mins.
 RTD 2690. Logs. 4 1/2" @ 2689 w/75 sx. PBTD 2687. MICT.
 P/24/2673-79, Ga 50 MCF, 1000 MA, Ga 200 MCF. Frac 8000-5% Ac X 8000 sd. Ga 1250 MCF + 4 BLWPH. Later Ga 986 MCF + 4 BLWPH, SIP 410.
 IP 1000 MCF, SIP 425, from Krider 2673-79.
 COMPLETE 8-28-61.

612312

LIBERAL ELECTRIC LOG TOPS

2887 KB

Krider 2620 (+267) ϕ IP = 1.000 MCF
TD 2690