


5-146W

MAP NO. SEC. 35TWP. 23SRGE. 31WSTATE Kans. COUNTY FinneyLOC. C SW/4OPERATOR Apache Corp.FT. FROM LINE WELL NO. 1 FARM NAME Snell UnitFT. FROM LINE 1 Hugoton Ext.ELEV. 2873GR. 2876DF. 2878E. KBFR. 3/14/62 SPUD 3/21/62COMP. 5/15/62CONT. Prime Drlg. Tools /GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
a					
b					
c					
d					

b	"	"	"	"	"
c	"	"	"	"	"
d	"	"	"	"	"

c	"	"	"	"	"
d	"	"	"	"	"

D & A D & A ()

SIP# FI TP # FI CP# SIBHP GOR. GR. PBD TD 2690

SIZE	DEPTH	CASING - CEMENT W/SAX.	RECORD SIZE	DEPTH	W/SAX.
8-5/8"	357	250			
4 1/2"	2689	100			

OPERATOR Apache Corp. WELL NO. 1 Snell Unit ELEV. 2878 EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
			Holl	2643	+ 235
RTD (Kri)	2690	+ 188	Herr	2671	+ 207
			Kri	2681	+ 197
DST #1 (Holl)	2650-90,		LTD		not available
	Op 1 1/2 hrs, GTS/20",				
	Ga 60 Mcfgpd, R 65' M, IBHP 465#/30", IFP 30#, FFP 30#,				
	FBHP 465#/30"				
RTD 2690, No Open Hole log, 4 1/2" @ 2689 w/100 sx. GRN Log					
4 way Jet 2670 (Perm) Swb dry, NS, 500A (15%) flush 41 BW,					
Swb 10 GAWPH, Ga 130 Mcfgpd, Frac 10,000 GA (2 1/2%) x 10,000#					
sd, Flush 52 BAW, Ga 346 Mcfgpd + 1d, Swb 200 B 1d, Ga 434					
Mcfgpd/8 hrs, SI 24 hrs, Ga 650 Mcfgpd + 2 1/2 BSWPH, Ga 822					
Mcfgpd + 3 BSWPH, Ga 619 Mcfgpd + 1 1/2 BSWPH, Flo 210 Mcfgpd					
+ wtr. Ga 400 to 200 Mcfgpd, hole 1d with wtr on 108 hr.					
test					

D & A - COMPLETE

612336

2878KB E-log Tops

w/krider 2674 (+204) D & A

TD 2690