


A 9-213

MAP NO. K-52 ELEV. 2875 KB
 STATE Kansas COUNTY Finney SEC. 15 Twp 23 S Rge 31 W
 OPERATOR W. C. McBride, Inc. - Tulsa LOC. C NW/4
 WELL NO. 1 FARM NAME Davis-Campbell Unit FT. FROM _____ LINE _____
 JL Hugoton (PD 2700) FT. FROM _____ LINE _____
 FR. 7-19-61 SPUD 7-24-61 COMP. 8-11-61

CONT./GEOL. Earl F. Wakefield

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a			
b			
c			
d			



a	I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"	"
c	"	"	"	"	"	"
d						

D & A

D & A [x]

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBDT _____ TD 2704

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>7-5/8"</u>	<u>332</u>	<u>200</u>			
<u>4 1/2"</u>	<u>2703</u>	<u>100</u>			

OPERATOR W. C. McBride WELL NO. 1 Davis-Campbell ELEV. 2875 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Anhydrite				1994	
Wellington				2435	
Hollenberg				2609	
Herrington				2639	
Upper Krider				2660	
Lower Krider				2696	

L.D. E1409
Kri 2660 +215

Spud 7-24-61. 7-5/8" @ 332 w/200 sx.
 DST # 1 (Kri) 2663-2704, op 60 mins, rec 30' M, ISIP 555/30 mins, FP 25-40, FSIP 290/60 mins.
 RTD 2704, logs (Sj). 4 1/2" @ 2703 w/100 sx.
 P/56/2670-84. 1000 MA. Frac 20,000 wtr X 20,000 sd. Swb 150 BL w/tr gas. Ga 500 MCF + 6 BSWPH. SQ 2670-84 w/150 sx.
 Re-P/36/2665-74. 500 MA. Swb 1d w/gst 50 MCF. Frac 20,000 wtr X 20,000 sd. Swb 235 BL w/GSG. Swb 2 1/2 BSWPH w/250 MCF
 Non commercial.

D & A 8-11-61.
 COMPLETE