

State Kansas County Reno

Company Messman-Rinehart Oil Co. Well No. 1

Farm Ira Johnson "A" (Washdown)


Survey _____

Block No. _____ Sec. 31 Twp. 23 S Range 10 W

Co-Ord. _____ Elev. 1803' R/F

Ctr. S/2 NW SE

M-R Rig



25% - A. A. Seeligson, Jr.
12.5% - A. A. Seeligson, Sr.
6.25% - Richard Gill
6.25% - Josephine L. Gill
25% - Chicago Group
25% - M-R Oil Co.

Washdown of Stano. #4 Ira C. Johnson @ 3804' R.T.D.
8-578 @ 264'

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
2/5/63		M.I.R.T.
2/6	3800	Washdown depth
2/7	3041	Washdown depth (prob on top of pipe)
2/8		Milling on 5 1/2" ppe
1:00 p.m.		Milling (40' over pipe)
		cut off csg. @ 3091
		Set 5 1/2" csg. w/sleeve at
		3091', CO & set plug @ 3400'
2/10		Logged hole & ran tbg.
13-13-S	3312	Lansing

Date	Depth	
2/11		Perf. 3336-40')
		3350-53' } 4 ^s ft.
		3358-60' }
		3364-67' }
		3000 acid, pressured up to
		800#, broke to 200#, treated
		@ 700# (broke)
		Total load 145 bbls.,
		swbd. & flowed 95 bbls. load
		back, had show gas & rainbow
		show oil
2/12/63		Dry & Abandoned