

State Geological Survey

WICHITA BRANCH

15-055-20291

KANSAS DRILLERS LOG

API No. 15 — 055 — 20,291
County Number

Operator

Amoco Production Company

Address

P. O. Box 432, Liberal, Kansas 67901

Well No.

2

Lease Name

O. G. Congdon

Footage Location

1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor

Damac Drilling Corporation

Geologist

Spud Date

2-17-78

Total Depth

5,000

P.B.T.D.

4960

Date Completed

4-25-78


Oil Purchaser

S. 28 T. 23 R. 32 E W

Loc. 1980' FSL X 1980' FWL

County Finney

640 Acres
N



Locate well correctly

Elev.: Gr. 2857

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	1590	Class "H"	750	6% Gel 2% CC 1/4# Flocele
Production	7 7/8	5 1/2	14#	5000	Special	1175	12.5# Gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	1/2	4807-4817
TUBING RECORD					4922-4926
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize with 750 Gal MCA with Floro Carbon Surfaction	4807-4817
Frac with 10,000 Gal Gelled KCL Water and 10,000 20% Retarded	4807-4817
HCL Acid.	

INITIAL PRODUCTION

Date of first production 4-25-78	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 15 bbls. Gas 9 bbls. MCF Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) 4807-5000

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Amoco Production Company

Well No.

Lease Name

2

O. G. Congdon

Oil

S 28 T 23 R 32 E^K
W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	40	Gamma-Correlation	4500-4960
Clay, Sand	40	1180		
Red Bed, Sand	1180	1591		
Shale	1591	2285		
Shale, Dolomite	2285	2484		
Shale	2484	2675		
Lime, Shale	2675	5000		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Gale McCord

Signature

Administrative Supervisor

Title

May 10, 1978

Date