

State **Kansas** County **Reno**

Company **Messman-Rinehart Oil Co.** Well No. **1**

Farm **Jean Johnson** 3100-101 - ob 5 11.2.79

Survey

Block No. 3179 Sec. 32 Twp. 23 S Range 10 W

Co-Ord. 3138 25° 29' (-122) Elev. 1786' D/E

NE/4 SE/4 SW/4

M-R Rig

50% - A. A. Seeligson, Jr.
25% - Chicago Group
25% - Messman-Rinehart Oil Co.

TIGHT

3800' Arbuckle test to be
comm. by 2/10/62

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 990

Ft. from S. Line

Ft. from W. Line 330

Ft. from E. Line

Date	Depth	
2/7/62		Location staked
2/8/62		M.I.R.T. - Spud
2/9		10-3/4' @ 205' w/175 sx. cem. 4 gel., 4 c.c., P.D. @ 3:30 a.m. 2/9/62
2/12	1685	Drlg.
		461-76 Anhydrite (#1327)
2/13	2080	Drlg.
2/15	2825	Drlg. (Mudded up 2/14/62) (visc. 36, wtr. loss 12)

Date	Depth	
	3100	Heebner (-1312)
	3166	Douglas (-1378)
	3250	Brown Lime (-1462)
	3282	Lansing (-1494) 14' high
2/16	3015	Drlg.
2/19	3490	Drlg.
2/20	3614	(On bank w/new bit)
	3628	Misener (-1840)
	3638	Viola (-1850) 28' high
	3642	Viola Dolomite (-1854) very small 50
	3655	Drlg.
2/21	3700	Drlg. (rough drlg))
	D.S.T. #1 - 3636-3720' - Op 1 hr.,	
	GTS in 12" (esti. 25,000 cf)	
	Rec. 120' gas-cut mud, 110°	
	BHP 109-93#, FP 62-62#, BHT	
	(depleted oil field)	
2/22	3729	Sp. Sh (-1941)
	3739	Sp. Sd (-1951)
	3748	D.D. (crse. sd., good odor, sho fr. oil, fair porosity)
	D.S.T. #2 - 3740-48' - Op 2 hrs.,	
	(30% tan sand ! wk. bl. to fr. bl., Rec.	
	70% white	
	510' GIP, 15' oil & gas-cut mud	
	75' mdy salt wtr.	
	BHP 413-327#, FP 31-5	

State Kansas County Reno

Company Messman-Rinehart Oil Co. Well No. 1


Farm Jean Johnson

Survey _____

Block No. _____ Sec. 32 Twp. 23 S Range 10 W

Co-Ord. _____ Elev. 1788' R/B

NE/4 SE/4 SW/4



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
2/23/62	3755	Drlg.
2/24	3800	Arbuckle (-2012)
		D.S.T. #3 - 3801-06' - Op 2 hrs.,
		Rec. 260' wtr., BHP 1235-
		1211#, FP 38-124#,
2/24	3816	R.T.D. (Welex Log)
		D & A 2/25/62