


State Kansas Field W.C.
 Company Champlin Refining Co. County FINNEY
 Farm W. E. LEAVITT No. 2
 Sec. 17 Twp. 23 S Range 34 W

Spot C. S. W. N. E.

Contractor W. L. HARTMAN

Remarks A. & B. test



Comm. 6/9/56 Comp. 8/15/56

Elev. 2975 GL 2077 KB 2077 TD 5744 PB

Pay 52 4694-4704

GRAVITY 30.5° Cor.

I.P. pump 50 bopd Press.

Casing Record: 13 3/8 7" 5742/200

20" 10 3/4 420/300 5 1/2"

16" 8 5/8

JUL 3	Sample	Log
<u>DST 4026-52 of 2 hrs</u>		
<u>rec 20' mud FPO BH 680/20</u>	<u>Heab 3839</u>	
<u>DST 4057-75 failed</u>	<u>Lany 3896</u>	
<u>DST 4059-76 of 2 hrs rec</u>	<u>BKC 4268</u>	
<u>120' WCM. + 80' SUL WAT. FPO</u>	<u>MARM 4302</u>	
<u>780 BHP 1060/20</u>	<u>Mar 4647</u>	<u>4651</u> ✓
<u>DST 4965-85 of 2 hrs rec 10'</u>	<u>SS 4698-4713</u>	<u>4692</u> ✓
<u>mud. passed</u>	<u>SS 4732-39</u>	<u>4726</u>
<u>DST 4700-30 of 2 hrs 975/hr</u>	<u>SS 4750-62</u>	<u>4743</u>
<u>10" TSPM rec 2032' gassy</u>	<u>ST. GEN 4786</u>	<u>4780</u> ✓
<u>oil + 400' OCM. FP 175 → 810</u>	<u>ST LOUIS 4836</u>	<u>VIOLA 5473</u>
<u>BHP 1070/15 oil qt above 30'</u>		<u>Simp 5636</u>
<u>DST 4733-67 of 2 hrs rec</u>	<u>300' muddy SW</u>	<u>ALB 5841</u>
<u>+ 1000' SW FPO → 455 BH 1095/20</u>		
<u>DST 4790-5023 of 2 hrs rec 10' mud FPO</u>	<u>BHP 0/20</u>	
<u>RTD 5744 - DST 5636-5744 of 2 hrs</u>	<u>rec 3620'</u>	
<u>oil water FP 380 → 1665 BHP 1665/20</u>	<u>now log</u>	
<u>at 7" @ 5742/200 WOC.</u>		
<u>RUGT CO to</u>	<u>ff 24/4710-16</u>	<u>ag w 200 surf.</u>
<u>CO to ?</u>	<u>ff 40/4694-4704</u>	<u>7hr SWB test made</u>
<u>46 BD. + 6% free water (B water?)</u>	<u>AET 7hrs WAS</u>	
<u>subbing to BOPH. - turning T + rods.</u>		
<u>AUG 15 P.D.P. - 17 hr pumped 6 BOPH.</u>	<u>30.5° gr. Cor.</u>	
<u>last pumped 45 BD in 24 hrs.</u>		

