

State Kansas County Reno

Company Messman-Rinehart Oil Co. Well No. 2

Farm Stroud


Survey _____

Block No. _____ Sec. 34 Twp. 23 S Range 5 W

Co-Ord. _____ Elev. 1513 KB
1511 DF

SE NW NW

M-R Rig



25% - Messman-Rinehart Oil Co
25% - Chicago Group
50% - A. A. Seeligson, Jr.

3850' Sp. test to be comm.
by 12-20-58

NOTE: Show Sketch of Lease and Well Location in Above Space

990 Ft. from N. Line Ft. from S. Line

990 Ft. from W. Line Ft. from E. Line

Date	Depth	
12-18-58		Spud - 10-3/4" @ 198' w/200 sx. cem., 3 gel, 4 c.c. P.D. @ 11:55 P.M. 12/18/58
12-19		WOC
12-20	810	Drlg.
12-22	1700	Drlg.
12-23	2200	Drlg. (#4 @ 2195)
12-24	2490	Drlg. (Shut down for Xmas)
12-27	2830	(Going in hole w/#6 bit)

Date	Depth	
		692257
12-28	3010	Drlg. (#7 bit @ 2990)
12-29	3170	Drlg. (#8 bit @ 3140)
12-30	3407	Going in w/#9 bit
12-31	3554	Drlg. (#10 bit @ 3464) #11 RR to ream
	3395	Miss. (-1882)
	3603	Kinderhook (-2090)
	3730	Hunton (-2217)
1-2	DST #1 - 3729-33	- Op 30", cl 15", Blow for 10 sec. & died, Rec. 5' mud, BHP (20") 40-0, FP 0-0#
	3765	Drlg.
	3759	Maquoketa (-2246) (1' higher than #1 Stroud) Drlg. 8-10 1/2/hr.
1-3	3831	Viola (-2318)
	3851	Sp. Sh. (-2338)
	3859	Sp. Sd. (-2346)
	3860	Drlg. (to dr. 10', log & plug
	3872	R.T.D. (Ran Welex Log) D & A - 1/4/59 Log Tops
	2488	Heebner
	2720	Lansing (-1200)
	3396	Miss. (-1883)
	3616	Kinderhook
	3738	Hunton (-2225)
	3764	Maquoketa
	3837	Viola (-2324)
	3860	Sp. (-2347)