

*9/11*

STATE CORPORATION COMMISSION OF KANSAS  
OIL & GAS CONSERVATION DIVISION  
WELL COMPLETION FORM  
ACO-1 WELL HISTORY  
DESCRIPTION OF WELL AND LEASE

Operator: License # 5952

Name: BP AMERICA PRODUCTION COMPANY

Address P. O. BOX 3092, WL1-RM 3.201

City/State/Zip HOUSTON, TX 77253-3092

Purchaser: \_\_\_\_\_

Operator Contact Person: SUE SELLERS

Phone ( 281 ) 366-2052

Contractor: Name: CHEYENNE DRILLING

License: 5382

Wellsite Geologist: \_\_\_\_\_

Designate Type of Completion

New Well  Re-Entry  Workover

Oil  SWD  SLOW  Temp. Abd.

Gas  ENHR  SIGW

Dry  Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Reentry: Old Well Info as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Comp. Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Deepening  Re-perf.  Conv. to Inj/SWD

Plug Back  PBSD

Commingled  Docket No. \_\_\_\_\_

Dual Completion  Docket No. \_\_\_\_\_

Other (SWD or Inj?)  Docket No. \_\_\_\_\_

3/15/03 3/16/03 5/7/03

Spud Date Date Reached TD Completion Date

API NO. 15- 093-21719-0000

County KEARNY

SW - SE - NE - NW Sec. 10 Twp. 23 S Rge. 36 X E W

1250 N Feet from S/N (circle one) Line of Section

2500 W Feet from E/W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
NE, SE, NW or SW (circle one)

Lease Name MORRIS Well # 2HI

Producing Formation CHASE

Formation: Ground 3121' KB 3127'

Total Depth 2806' PBSD 2806'

Amount of Surface Pipe Set and Cemented at 826 Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set \_\_\_\_\_ Feet

If Alternate II completion, cement circulated from \_\_\_\_\_

feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content 8500 ppm Fluid volume 700 bbls

Dewatering method used DRIED AND FILLED

Location of fluid disposal if hauled offsite: \_\_\_\_\_

Operator Name \_\_\_\_\_

Lease Name \_\_\_\_\_ License No. \_\_\_\_\_

\_\_\_\_\_ Quarter Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S Rge. \_\_\_\_\_ EW

County \_\_\_\_\_ Docket No. \_\_\_\_\_

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Sue Sellers


Title STAFF ASSISTANT Date 05/12/03

Subscribed and sworn to before me this 12TH day of MAY

20 03

Notary Public Helen K. Zapalac

Date Commission Expires \_\_\_\_\_



K.C.C. OFFICE USE ONLY		
F	<input type="checkbox"/>	Letter of Confidentiality Attached
C	<input type="checkbox"/>	Wireline Log Received
C	<input type="checkbox"/>	Drillers Timelog Received
Distribution		
<input type="checkbox"/>	KCC	<input type="checkbox"/> SWD/Rep <input type="checkbox"/> NGPA
<input type="checkbox"/>	KGS	<input type="checkbox"/> Plug <input type="checkbox"/> Other
(Specify)		

Operator Name BP AMERICA PRODUCTION COMPANY Lease Name MORRIS Well # 2HI

Sec. 10 Twp. 23S Rge. 36W  
 East  
 West

County KEARNY

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken (Attach Additional Sheets.)  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No  
 Electric Log Run (Submit Copy.)  Yes  No  
 List All E.Logs Run:  
 COMPENSATED SPECTRAL NATURAL GAMMA

Log Formation (Top), Depth and Datums  Sample  
 Name Top Datum  
 CHASE 2532' KB

CASING RECORD  New  Used  
 Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12 1/4"	8 5/8"	24#	826'	HL 'C' PP	250 SXS	3%CC:1/4#FLOC
					HL 'C' PP	125 SXS	2%CC:1/4#FLOC
PRODUCTION	7 7/8"	4 1/2"	10.5#	2806'	HL 'C' PP	550 SXS	1/4# FLOCELE

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	2696-2716'	FRAC-150,300# 16/30 BRADY SAND & 769,000' OF N2 Q80 FOAM	2696-2716

TUBING RECORD Size 2 3/8" Set At 2731' Packer At NA Liner-Run  Yes  No

Date of First, Resumed Production, SWD or Inj. 5/7/03 Producing Method  Flowing  Pumping  Gas Lift  Other (Explain)  
 Estimated Production Per 24 Hours Oil 0 Bbls. Gas 106 Mcf Water 0 Bbls. Gas-Oil Ratio Gravity

Disposition of Gas:  Vented  Sold  Used on Lease  Open Hole  Perforation  Dually Comp.  Commingled  
 (If vented, submit ACO-18.)  Other (Specify)