


90062 ✓

9-167W
 STATE Kans MAP NO. 51 SEC. 23-23S-36W
 COUNTY Kearny LOC. C SE NW
 OPER. Pan American Pet Corp - Ulysses, Kansas FT/FR _____ LINE _____
 WELL 1 FARM C.H. Hoover FT/FR _____ LINE _____
 JL Geol WC ELEV. 3127 GR. 3134 OF 3137 KB
 JNT. Big Chief Drlg. GEOL. Herb Davis
 CO. INT. 5100' Miss Test
 F.R. 8-16-63 SPUD 8-20-63 COMP. 9-17-63
 TD. 5201 FM. Salem PBTD. _____



COMP. RECORD D&A
Geol WC-Hugoton Field - 9½ mi SW of Amazon Ditch (Miss Oil)
8 5/8" @2087 w/1250 sx. *Data Inc.*

(KB Sp1)			(KB Log)		
Herr	2538		Chase	2536	+ 601
Kri	2558		CG	2824	+ 313
Winf	2592		Mo	3858	- 721
Tow	2658		Des M	4386	-1249
FR	2700		Morr	4748	-1611
CG	2815		Morr sd	4906-24	-1769
RTD	5201	-2064	St Gen	4928	-1791
			St L	4984	-1847
			1st LTD	NA	
			(Cont)		
			Salem	5130	-1993
			2nd LTD	NA	

DST #1 (CG) 2745-2817, Op 30", WB/NT, R 55' GCM, ISIP 560#/NT,
IFP 66#, FFP 66#, FSIP 400#/NT, Ran Log, (Temp TD 5100)
WLT #1 (Mo) 4087, Op 90", R 6700 cc wtr (7% form wtr), ISIP
1100#/22", SP less than 50", FSIP 1100#/13", RTD 5201
(Salem), Ran 2nd E Log - D&A - COMPLETED (9-5-63)

2137
 2592
 545

AMARILLO ELECTRIC LOG TOPS

612881

3137 KB

Winfield 2591 (+546)
 Council Grove 2814 (+323) DST GCM
 Heebner 3800 (-663)
 Toronto 3824 (-687)
 Lansing 3858 (-721) WLT/Fm Wtr
 Marmaton 4387 (-1250)
 Morrow 4753 (-1616)
 "S-3" 4904 (-1767) 15/18; NT
 Ste. Gen 4928 (-1791)
 St. Louis 4943 (-1806)
 Spergen (Opr) 5130 (-1993)
 RTD 5201 D & A

(Below), Ran and R Log - COMPLETED (2-2-61)
 1100+1220, 2P less than 50", 1000+1100, RLD 2000
 WLT #1 (Gm) 4087, Op 50", R 5700 so wt (100 lbm wt), 151P
 11P 600, 11P 600, 11P 600, 11P 600, 11P 600, 11P 600
 DST #1 (Gm) 2745-1117, Op 100", WLT, R 557, GCM, 11P 600, 11P 600, 11P 600