

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

3-23-37W

Company- STANOLIND OIL & GAS CO.
Farm Powers Gas Unit No. 1


SEC. 3 T. 23 R. 37W
C SW/4

Total Depth. 2731
Comm. 11-5-54
Shot or Treated.
Contractor.
Issued. 1-1-55

PBTD 2704
Comp. 11-27-54

County Kearny

KANSAS



CASING:

8 5/8 @ 825' w/ 400 sx cmt.
5 1/2 @ 2695' w/ 1000 sx cmt.

Elevation. 3268 DF

Production. 7,108,000 Gas

Figures indicate Bottom of Formations.

surface sand & clay	145
sand	210
shale & shells	425
shale & sand	600
shale	820
red bed	827
red bed & shale	1033
red bed & sand	1280
anhydrite & shale	1575
shale	1710
anhydrite	1770
shale	1910
red shale	1950
shale & lime	2095
shale	2285
lime & shale	2350
lime	2505
shale & lime	2605
lime	2731
Total Depth	

Treated Winfield w/ 250 gal dolowash
3000 gal dolofrac gel 12% w/ 6000#
sand, 1500 gal dolowash, flushed
w/ 600 gal water.
Treated Herington-Krider w/ 250 gal.
doloflush, 3000 gal dolofrac gel 12%
w/ 6000# sand, 1500 gal dolowash,
flushed w/ 600 gal water.

Perf w/ 6 SPF as follows:
Towanda, 2672-78, 2659-68
Winfield 2642-49, 2627-30, 2616-21,
2600-13
Herington-Krider 2574-78, 2565-69,
2550-61

TOPS:

Herington-Krider	2548
Winfield	2600
Towanda	2659
Ft. Riley	2695

Schlumberger ran Gamma Ray & Micro-
log.

Treated well as follows:

Ft. Riley down hole w/ 250 gal dolo-
flush, 3000 gal dolofrac gel 12% w/
5000# sand, 1250 gal dolowash, flushed
w/ 2800 gal water. packer set @ 2704
to shut off water
Treated Towanda w/ 250 gal doloflush,
3000 gal dolofrac gel 12% w/ 6000#
sand, 1500 gal doloflush, flush w/
600 gal water.