

9-23-37W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL  
Farm- Bell "B" No. 1

SEC. 9 T. 23 R. 37W  
NE NE SW

Total Depth. 2720'  
Comm. 12-21-55 Comp. 12-28-55  
Shot or Treated.  
Contractor. Holm Drlg.  
Issued. 10-10-59

County Kearny  
KANSAS



Elevation. 3665' DF

Production. 4,050,000 CFG

CASING:

8 5/8" 840' cem w/500 sx.  
5 1/2" 2711' cem w/600 sx.

Figures indicate Bottom of Formations.

clay, sand	99
sand	295
sand, shale	405
sand, shale	600
shale	815
red bed	845
red bed, shells	1285
Anhydrite	1305
shale, shells	1640
shale, shells	2073
lime, shale	2720 RTD
Total Depth	

TOPS: LOG

Morrow	2544
Winfield	2584
Upper Ft. Riley	2644
Lower Ft. Riley	2702

Perf. 40/2644-54, 56/2586-2600, 44/2546-2555,  
frac/1000 gal, frac/6000 gal, sd/12,000, wash/  
3000, jet wash, wtr/2675